

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

4 15-065-03145-0001

API NUMBER 6-30-59

LEASE NAME Elrick Unit

WELL NUMBER 6-7

330' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 10 TWP. 10S RGE. 25 XXXX(W)

COUNTY Graham

Date Well Completed 7-59

Plugging Commenced 10-18-91

Plugging Completed 10-25-91

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Citation Oil & Gas Corp.

ADDRESS 8223 Willow Place South Ste 250 Houston, TX 77070

PHONE#(713) 469-9664 OPERATORS LICENSE NO. 03553

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 14, 1991 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? submitted with notice to plug

Producing Formation Toronto LKC Depth to Top 3748' Bottom 3962' T.D. 4215'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
Toronto		3748	3770	8 5/8"	114'	0
LKC		3792	3962	5 1/2"	4024'	0

RECEIVED

STATE CORPORATION COMMISSION

DEC 6 1991

12-6-91

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.  
Drilled Iron Sulfide from 1450'-3941'. Ran tbq to 2916' & broke circulation. Ran tbq to 3905' pumped 90 sx cmt w/400 lbs Hulls. POOH to 2122' & perf'd @ 2150'. Pumped 100 sx cmt. Pulled tbq to 1196' & perf'd @ 1250'. Circulated cmt to surface w/150 lbs Hulls. Put swedge on 5 1/2" csg & pumped 70' sx + 200 lbs Hulls. Tied on to 8 5/8" csg & pmp'd 80 sx + 100 lbs Hulls.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Leon's Cable Tool Rig/ Citation License No. unknown

Address 4848 S.W. 36TH Street Oklahoma City, OK 73179

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp.

STATE OF Texas COUNTY OF Harris, ss.


Sharon E. Ward (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon E. Ward

(Address) 8223 Willow Place South Ste 250 Houston Texas 77070

AND SWORN TO before me this 4th day of December, 19 91

Carole Favro  
 Notary Public



Commission Expires: 3-2-95