

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-03245-0000

API NUMBER 15-N/A

LEASE NAME Elrick

WELL NUMBER 7-8

330 Ft. from S Section Line

330 Ft. from W Section Line

SEC. 10 TWP. 10S RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 10-22-58

Plugging Commenced 8-25-93

Plugging Completed 8-25-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Citation Oil & Gas Corp.

ADDRESS 8223 Willow Place S. Ste 250 Houston, Texas 77070

PHONE#(713) 469-9664 OPERATORS LICENSE NO. 03553

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 22, 1993 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? log filed with intent to plug

Producing Formation LKC Depth to Top 3764 Bottom 3988 T.D. 4005

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	3764	3988	8 5/8"	148	0
				5 1/2"	4004	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. On 8-26-93 Citation MIRU perf'd 3 shots @ 2150', perf'd 3 shots @ 1248'. Tagged PBTD @ 3988'. RU cmtrs & spotted 90 sx 60/40 Poz + 1/4# FlowSeal+400# hulls. Spotted 100 sx 60/40 Poz + 1/4# FlowSeal +200 # hulls @ 2156'. POOH LD tbg to 1250'. Circulated cmt to surface w/130 sx 60/40 Poz + 1/4# FS. Pmp'd 150 sx 60/40 Poz + 1/4# FS down 8 5/8" csg. Pressure tested OK. Pmp'd 150 sx cmt+additive down 5 1/2" csg. Sqz'd to 600#. Cut & cap'd well. Cleaned location. Well P&A'd.

Name of Plugging Contractor Halliburton Services License No. 5287

Address 4848 SW 36th Street Oklahoma City, OK 73179

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp.

STATE OF Texas COUNTY OF Harris, ss.

Sharon Ward (Employee of Operator) or (Operator) of above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
AUG 30 1993

(Signature) Sharon Ward

(Address) 8223 Willow Place S. Ste 250

Houston, Texas 77070

Subscribed and sworn to before me this 26 day of August, 19 93

Renee Harrell

Notary Public

SUBSCRIBED AND SWORN TO before me this

RENEE HARRELL
MY COMMISSION EXPIRES
March 2, 1995

Expires: 3-2-95

