

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-03143-0001

API NUMBER 12-12-58

LEASE NAME Elrick Unit

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 6-5

990 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 10 TWP. 10S RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 12-12-58

Plugging Commenced 10-25-91

Plugging Completed 10-31-91

LEASE OPERATOR Citation Oil & Gas Corp.

ADDRESS 8223 Willow Place South Ste 250 Houston, TX 77070

PHONE#(713) 469-9664 OPERATORS LICENSE NO. 03553

Character of Well injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 14, 1991 (date)

by David P. Williams and witnessed by KCC representative (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Log submitted with proposal

Producing Formation Lansing Kansas City Depth to Top 3772 Bottom 3985 T.D. 4230

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put In	Pulled Out
Toronto	Oil	3766	-	8 5/8"	152	0
Lansing	Oil	3780	-	5 1/2"	4023	0
Base Kansas City	Oil	4010	-			

STATE CORPORATION COMMISSION
NOV 12 1991
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Drilled thru CIBP's @ 3900', mixed & pumped 175 bbls mud. Pushed plug to 3969'. Ran tbg to 3905', broke circulation & pumped 90 sx cmt w/400 # hulls. POOH & perfed 3 holes @ 2150'. Pumped 100 sx cmt. POOH and perfed 3 holes @ 1250'. Pumped 40 sx cmt and circulated cmt to surface. Put swedge on csg & pumped 35 sx cmt w/100# hulls down csg. Pressured to 1100 psi. Pumped down back side w/100 sx cmt and 100# hulls. Pressured. Well plugged on 10-31-91.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address 1108 East 8th Street, Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp.

STATE OF Texas COUNTY OF Harris, ss.


Sharon E. Ward (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon E. Ward

(Address) 8223 Willow Place South Ste 250 Houston, Texas 77070

SUBSCRIBED AND SWORN TO before me this 8th day of November, 19 91

Renee Harrell
Notary Public



My Commission Expires: 3-2-95