

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-03248-0001

API NUMBER 15-N/A

LEASE NAME Elrick

WELL NUMBER 6-3

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 10 TWP. 10 RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 1958

Plugging Commenced 8-13-93

Plugging Completed 8-13-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Citation Oil & Gas Corp.

ADDRESS 8223 Willow Place South Ste 250 Houston, TX 77070

PHONE# (713) 469-9664 OPERATORS LICENSE NO. 03553

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-22-93 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached? filed w/intent to plug

Producing Formation LKC Depth to Top 3766 Bottom 3984 T.D. 4005

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC		3766	3984	8 5/8"	150	0
				5 1/2"	4003	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Tagged TD @ 3801'. Pmp'd 90 sx 60/40 Poz cmt+10%gel+1# FlowSeal w/400# huls. Disp.w/8bbl wtr.
@ 2125' perf'd 3 shots. @ 2140' pmp'd 100 sx 60/40 Poz+additives+200# huls. @ 1218' perf'd 3 shots.
@ 1240' pmp'd 75 sx 60/40 Poz+additives. Cic to surf on 51csg. Pmp'd 150" sx 60/40 Poz + additives.
other side (if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No.

Address 1108 East 7th Street Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp.

STATE OF Texas COUNTY OF Harris, ss.

Sharon Ward

(Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon Ward

(Address) 8223 Willow Place S. Ste 250 Houston

TX 77070

SUBSCRIBED AND SWORN TO before me this 13th day of August, 19 93



Renee Harrell
Notary Public

Commission Expires: 3-2-95

continued from front side:

down 8 5/8" csg. Pump'd 20 sx 60/40 Poz + additives down 5½" csg sqz'd to 500#.

cut & capped well. Cleand location. Well P&A'd on 8-13-93