

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-065-03147-0001  
 API NUMBER 11-7-58

LEASE NAME Elrick Unit

WELL NUMBER 12-3

1650 Ft. from <sup>N</sup> Section Line

1650 Ft. from E Section Line

SEC. 10 TWP. 10 RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 3-12-59

Plugging Commenced 8-2-94

Plugging Completed 8-3-94

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Citation Oil & Gas Corp.

ADDRESS 8223 Willow Place South Ste 250

PHONE#(713) 469-9664 OPERATORS LICENSE NO. 03553

Character of Well Inj

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-28-94 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? sent in w/CP-1

Producing Formation N/A Depth to Top 3777 Bottom 4002 T.D. 4242

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS:

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
N/A	N/A	-	-	8 5/8	156	0
				5 1/2	4232	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RIH to 3640' moved CIBP down to 3665'. Could not push CIBP dn to 3903'. RIH to 2150' & shot 3 sqz holes. Pmp'd 200 sx CL "A" w/6% gel & 400# hulls from 3900'. TOOH to 1500' & pmp'd 175 sx CL "A" w/ 6% gel to surf. Sqz'd 150 sx "A" + 6% gell dn 8 5/8" csg. Cut & placed ID marker.

KCC rep Dennis Hamel OK'd the depth of 3903. KCC rep. Marion Schmidt changed procedure.  
 (If additional description is necessary, use BACK of this form.)

RECEIVED  
 KANSAS CORPORATION COMMISSION

Name of Plugging Contractor Halliburton Services License No. 5287

Address 1108 East 8th Street Hays, KS 67601.

AUG 08 1994

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp.

STATE OF Texas COUNTY OF Harris, ss.

CONSERVATION DIVISION  
 WICHITA, KS

Sharon Ward (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon Ward

(Address) 8223 Willow Place S. Ste 250  
 Houston, Texas 77070

SUBSCRIBED AND SWORN TO before me this 4th day of August, 19 1994

Renee Harrell  
 Notary Public



Commission Expires: 3-2-95