

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-03286-0000

API NUMBER 15-N/A

LEASE NAME Elrick Unit

WELL NUMBER 4-2

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 15 TWP. 10 RGE. 25 (E or W)

COUNTY Graham

Date Well Completed 9-24-58

Plugging Commenced 1-15-96

Plugging Completed 1-15-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Citation Oil & Gas Corp.

ADDRESS 8223 Willow Place South Ste 250

PHONE (281) 469-9664 OPERATORS LICENSE NO. 03353

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 17, 1996 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? Submitted w/intent

Producing Formation LKC Depth to Top 3752 Bottom 3970 T.D. 3992

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Oil	3752	2970	8 5/8	205	0
				5 1/2	3992	1002

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, -from feet to feet each set
MI RU PU. Perf'd @ 2150 & 1300' 1 shot. Pump'd 20 sxs 60/40 Poz w/10% gel +300 # hulls. Tailed w/80 sxs 60/40 Poz +10% gel displaced to 1200'. Shot off csg @ 1002'. Pump'd 80 sxs 60/40 Poz w/10% gel +150 # hulls. Displaced w/2 BW. POOH w/31 its 5 1/2" prod. csg. Circ. cmt to surf w/20 sxs 60/40 Poz w/10% gel. POOH w/2 its 5 1/2" csg. Top csg off w/cmt. RD PU. OK'd by Carl Gudrow. P&A'd on 1-15-97

1-28-97

Name of Plugging Contractor Haliburton Services License No. 1-28-97

Address 1102 East 8th Street Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp.

STATE OF Texas COUNTY OF Harris, ss.

Sharon Ward of Citation Oil & Gas Corp.


(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Sharon Ward

8223 Willow Place S. Ste 250

(Address) Houston, Texas 77070



RENEE HARRELL

Notary Public State of Texas

My Commission Expires March 2, 1999

AND SWORN TO before me this 24th day of January, 19 97

Renee Harrell
Notary Public

3-2-99

My Commission Expires:

USE ONLY ONE SIDE OF EACH FORM