

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-20201-0006

API NUMBER 2-8-69

LEASE NAME Elrick Unit

WELL NUMBER 3-4

+1000 Ft. from S Section Line

+297 Ft. from W Section Line

SEC. 15 TWP. 10 RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 2-7-69

Plugging Commenced 8-12-94

Plugging Completed 8-13-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Citation Oil & Gas Corp.

ADDRESS 8223 Willow Place South Ste 250 Houston, TX 77070

PHONE#(713) 469-9664 OPERATORS LICENSE NO. 03553

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-28-94 (date)

by Marvin L. Miller (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? sent in with intent to plug

Producing Formation N/A Depth to Top 3738 Bottom 3976 T.D. 3987

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		3738	3976	8 5/8	192	0
				5 1/2	3987	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 5 1/2" csg set plug #1 @ 3829-3796 w/100 sx std cmt + 400\$ hulls throughout. POOH w/tbg to 2119'. Perf'd 3 holes @ 2150'. Plug #2 @ 2150-2119 w/100 sx 40/60 Poz + 8% gel +200 # Hulls. POOH w/tbg to 1202'. Perf'd 3 holes @ 2140'. Plug #3 @ 1240-1202 w/75 sx 40/60 Poz +8% gel. POOH w/all tbg. Plug #4 @ 1240-surface. In 5 1/2" csg pmp'd 100 sx 40/60 Poz + 8% gel + 100# hulls. Pmp'd dwn 8 5/8'
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address 1108 East 8th Street Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp.

STATE OF Texas COUNTY OF Harris, ss.


Sharon Ward (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon Ward

(Address) 8223 Willow Place South Ste 250 Houston, Texas 77070

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 94

My Commission Expires: 8/30/97



RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1994
CONSERVATION DIVISION
WICHITA, KANSAS

csg from surface w/ 65 sx 40/60 Poz + 8% gell. Shut in w/100# pressure. Hooked up to 5½" csg & pmp'd 60 sx 40/60 Poz w/8% gel. Called KCC w/ report. Well P&A'd on 8-13-94

