

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-005-03288-0000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Elrick
WELL NUMBER 3-4A
 Ft. from S Section Line
 Ft. from E Section Line

LEASE OPERATOR Citation Oil & Gas Corporation
ADDRESS 4848 SW 36th Street Oklahoma City, Ok 73179
PHONE (405) 681-9400 OPERATORS LICENSE NO. 03553

SEC. 15 TWP. 10S RGE. 25 (E)(X)(W)
COUNTY Graham
Date Well Completed
Plugging Commenced 2-29-96
Plugging Completed 3-1-96

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)
The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3991'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	194'	none
				5 1/2"	3991'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each section.
Ran 2-7/8" tubing to 1800', pumped 60 sacks cement with 300# hulls, pulled to 900', pumped 60 sacks cement with 200# hulls, pulled tubing out, pumped 20 sacks cement down Ann., pressure up to 400 psi, close in, pumped 20 sacks cement down 5-1/2", pressure up to 450# psi, close in. Plugging complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529
Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp. Oklahoma City, Ok. 73179
STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*
(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 15th day of March, 19 96

Jane Terzberg
Notary Public

My Commission Expires:



RECEIVED
KANSAS CORP. COMM
11:28
Form 07
Revised 05-