

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Elrick Unit
 WELL NUMBER 3-2
4950 Ft. from S Section Line
990 Ft. from E Section Line
 SEC. 15 TWP. 10 RGE. 25 (or (W))
 COUNTY Graham
 Date Well Completed 6-17-58
 Plugging Commenced 1-14-97
 Plugging Completed 1-14-95

LEASE OPERATOR Citation Oil & Gas Corp.
 ADDRESS 8223 Willow Place South Ste 250
 PHONE#(281) 469-9664 OPERATORS LICENSE NO. 03353

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on September 17, 1996 (date)
 by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? Submitted w/intent
 Producing Formation LKC Depth to Top 3756 Bottom 3995 T.D. 4024

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Oil	3756	3995	8 5/8	237	0
				5 1/2	4024	875

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, -from feet to feet each set
MI RU PU. RU WL. RIH w/5 1/2" CIBP @ 3675'. RIH dump'd 5 sxs cmt on top. Loaded hole w/89 BW. RIH perf'd 1 shot @ 2505 & 1308. Pump'd 20 sx 60/40 Poz+10% gel displaced to 1200'. Shot off csg @ 1008' not free. SHot 5 1/2" csg off @ 875'. Pump'd 80 sxs 60/40 Poz w/10% gel. POOH w/25 jts 5 1/2" prod. csg. Circ. cmt to surf w/30 sxs 60/40 Poz w/10% gel. POOH w/2 jts 5 1/2" csg. RD PU. Rec.27 jts 5 1/2" prod. csg. KCC Carl Gudfow approved procedure. Well P&A'd on 1-14-97

Name of Plugging Contractor Haliburton Services License No. 1-23-97
 Address 1102 East 8th Street Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp.
 STATE OF Texas COUNTY OF Harris, ss.

Sharon Ward of Citation Oil & Gas Corp. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon Ward
 8223 Willow Place S. Ste 250
 (Address) Houston, Texas 77070



SWORN TO before me this 24th day of January, 19 97
Renee Harrell
 Notary Public

My Commission Expires: 3-2-99
 USE ONLY ONE SIDE OF EACH FORM