


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 15 Twp. 10 Rge. 25W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Herndon Drilling Company
Lease Name J. F. Pfeifer Well No. 1
Office Address Drawer 489, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/23/58 19
Application for plugging filed 4/23/58 19
Application for plugging approved 4/23/58 19
Plugging commenced 4/23/58 19
Plugging completed 4/23/58 19
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Al Fabricous, Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4025 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 500 feet to 240 feet for each plug set. and 40 ft.

Hole was filled with rotary mud to 500 feet. Plug was set and cemented with 25 sx. cement, mixed and pumped in with Halliburton Cementing Co. Hole was filled to 240 ft. with heavy rotary mud. Plug was set and 15 sx. cement was mixed and pumped in by Halliburton. Hole was filled to 40 ft. and plug was set and 10 sx. cement was mixed and pumped in by Halliburton. Job completed 4/23/58.

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 1958

CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Herndon Drilling Company
Address Drawer 489, Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss. Tom Elliott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Tom Elliott
Drawer 489, Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of April, 19 58

My commission expires



Judy Kiefer Notary Public.

PLUGGING
FILE SEC. 15 T. 10 R. 25W
BOOK PAGE 97 LINE 9

WELL LOG

Well: J. F. PFEIFER NO. 1
 Location: SE SE SE, Section 15-10S-25W
 Graham County, Kansas
 Owner: Herndon Drilling Company, et al

Spudding date: 4/14/58
 Date casing set: 4/15/58
 Date rotary completed: 4/23/58
 Date cable completed: None

FROM	TO	FORMATION	REMARKS
0	254	Surface Hole	Set 9 Jts. 8-5/8" 24# Casing at 254' w/175 sx. common cement w/2% C.C.
254	540	Shale	
540	1775	Shale & Shells	
1775	2100	Shale, Shells & Lime	
2100	2145	Anhydrite	
2145	2347	Shale & Shells	
2347	2925	Shale & Lime	
2925	3115	Lime	
3115	3747	Lime & Shale	
3747	4025	Lime	
4025		Total Depth	Plugged hole 4/23/58: First plug @ 500' w/25 sx. cement Second plug @ 240' w/15 sx. cement Third plug @ 40' w/10 sx. cement

PLUGGING

FILE: DEC 15 T 10 R 25 W

BOOK PAGE 97 LINE 9

Subscribed and sworn to before me this 28th
 day of April, 1958

I certify the above and foregoing to be a true and exact copy
 of the original driller's log on the J. F. Pfeifer #1.

Judy Pfeifer
 Notary Public
 My commission expires: 1/27/60

HERNDON DRILLING COMPANY

C J Moore
 By: _____
 Title: **Assistant Secretary**