

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

TREGO County, Sec. 34 Twp. 12 Rge. 22 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE 1/4, NW 1/4, NE 1/4

Lease Owner Schafer Drilling Company

Lease Name Anderson (Deutscher) Well No. 1

Office Address Box 350--Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-7-53 19

Application for plugging filed 12-8-53 19

Application for plugging approved 12-8-53 19


Plugging commenced 12-8-53 19

Plugging completed 12-8-53 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4060 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	3596		8 5/8	250' 6"	None
Lansing-K.C.	Dry	3626				
Marmaton	Dry	3921				
Arbuckle	Dry	4023				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with heavy mud to 240 feet and plug was set. Twenty-five (25) sacks of cement were then hand mixed and poured through the drill pipe on top of the plug.

Hole was then filled to 40 feet and plug was set. Ten (10) sacks of cement were then hand mixed and put on top of the plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SCHAFER DRILLING COMPANY
Address BOX 350--PRATT, KANSAS

STATE OF KANSAS, COUNTY OF PRATT, SS.
James E. Selby (employee of owner)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James E. Selby
PRATT, KS. (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of DECEMBER 19 53

My commission expires February 25, 1956
Hilda Coulter Notary Public.

PLUGGING
FILE SEC 34 T 12 R 22W
BOOK PAGE 148 LINE 27


12-17-1953

15-195-01093-00-00

DRILLERS' LOG
DEUTSCHER (ANDERSON) #1
W $\frac{1}{2}$, NE $\frac{1}{4}$, 34-12S-22W
Trego County, Kansas

Commenced November 17, 1953
Completed December 7, 1953.

0-65	Shale & Gravel
65-150	Shale
150-250	Shale & Shell
250-910	Shale
910-1225	Sand
1225-1460	Shale & Sand
1460-1660	Shale & Shell
1660-1740	Red Bed
1740-1780	Lime
1780-1985	Shale & Shell
1985-2480	Shale & Shells
2480-2600	Lime
2600-2695	Shale & Lime
2695-2745	Lime
2745-3050	Shale & Lime
3050-3125	Lime
3125-3225	Shale & Lime
3225-3440	Lime
3440-3505	Shale & Lime
3505-3860	Lime
3860-3940	Shale & Lime
3940-3975	Lime
3975-3995	Shale, Lime & Chert
3995-4060	Lime
4060	TOTAL DEPTH



12-17-1953