

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

15-065-03152-0000

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # ~~4-001-729~~ 1960 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Citation Oil & Gas Corp. KCC LICENSE # 3553 ^{9/96}
(owner/company name) (operator's)

ADDRESS 8223 Willow Place South Ste 250 CITY Houston

STATE Texas ZIP CODE 77070 CONTACT PHONE # (713) 469-9664

LEASE Elrick WELL# 13-2 SEC. 10 T. 10 R. 25 (~~East~~/West)

SW - NE - NE - SPOT LOCATION/XXXX COUNTY Graham

+1650 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

+990 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 196 CEMENTED WITH 165 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 4237 CEMENTED WITH 50 cmt/600 latex SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3760'-3766' 3804'-4230' CIBP @ 4050'

ELEVATION 2493 GL T.D. 4238 PBTB 4050 ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

- PROPOSED METHOD OF PLUGGING
1. TIH w/ 2 1/2 tbg OE to PBTB (4050'). Spot 50 sx cmt plug. Leave TOC @ 3500'.
 2. POOH w/tbg.
 3. Shoot off csg @ 1200'. Mix & pump 150 sx plug w/300# hulls.
 4. POOH to 250'. Mix & pump 50 sx cmt and circulate to surf. POOH LD csg.
 5. Cut off wellhead 3' BGL & weld on P&A plate.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? unknown

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. ⁹⁻¹⁷⁻⁹⁶ AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Chris Morro PHONE# (713) 469-9664

ADDRESS 8223 Willow Place South Ste 250 City/State Houston, Texas 77070

PLUGGING CONTRACTOR Halliburton Services KCC LICENSE # 5287
(company name) (contractor's)

ADDRESS 1108 East 8th Street Hays KS 67601 PHONE # () _____

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9-12-96 AUTHORIZED OPERATOR/AGENT: Saron Ward
(signature)

4



15-065-03152-0000

Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 17, 1996

Citation Oil & Gas Corporation
8223 Willow Place South Ste 250
Houston TX 77070

Elrick #13-2
API 15-N/A
1650 FSL 990 FEL
Sec. 10-10S-25W
Graham County

Dear Chris Morro,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #4
2301 E 13th
Hays KS 67601
(913) 628-1200