

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

15-065-03286-0000  
FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # ~~4-001-717~~ N/A (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Citation Oil & Gas Corp. KCC LICENSE # 3553 9/96  
(owner/company name) (operator's)

ADDRESS 8223 Willow Place South Ste 250 CITY Houston

STATE Texas ZIP CODE 77070 CONTACT PHONE # (713) 469-9664

LEASE Elrick Unit WELL# 4-2 SEC. 15 T. 10 R. 25 (E/W/West)

NE - SE - NW - SW SPOT LOCATION/QQQQ COUNTY Graham

±990 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

±330 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 205 CEMENTED WITH unknown SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3992 CEMENTED WITH unknown SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3752'-3970' CIBP @ 3705'

ELEVATION - T.D. 3992 PBSD 3705 ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

- PROPOSED METHOD OF PLUGGING \_\_\_\_\_
1. TIH w/Bailer & dump 25' cmt on top of CIBP (3705').
  2. Shoot off csg @ 1200'. Mix & pump 150 sx plug w/300# hulls.
  3. POOH to 50' below surface csg & circulate cmt. POOH ED csg.
  4. Cut off wellhead 3' BGL & weld on P&A plate.
- (If additional \_\_\_\_\_)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? unknown  
If not explain why? no log

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Chris Morro PHONE# (713) 469-9664

ADDRESS 8223 Willow Place South Ste250 City/State Houston, Texas 77070

PLUGGING CONTRACTOR Halliburton Services KCC LICENSE # 5287

ADDRESS 1108 East 8th Street Hays KS 67601 PHONE # ( ) \_\_\_\_\_  
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) \_\_\_\_\_

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9-12-96 AUTHORIZED OPERATOR/AGENT: Sharon Ward  
(signature)

4



15-065-03286-0000

---

## Kansas Corporation Commission

---

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 17, 1996

Citation Oil & Gas Corp  
8223 Willow Place South Ste 250  
Houston TX 77070

Elrick Unit #4-2  
API 15-N/A  
990 FSL 330 FEL  
Sec. 15-10S-25W  
Graham County

Dear Chris Morro,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams  
Production Supervisor

District: #4  
2301 E 13th  
Hays KS 67601  
(913) 628-1200