

\$158.34

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21571-00-00  
Spot: SENW Sec/Twnshp/Rge: 13-27S-18W  
1980 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: LEISS GAS UNIT A Well #: 1-13  
County: KIOWA Total Vertical Depth: 4872 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4710		
SURF	8.625	375		WITH 300 SX CMT
	PLG 4.5	4819		
	PROD 4.5	4870	2650	WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2009 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4630' & 4 SX CMT. PLUG AT 1170' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/24/2009 1:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BACK TO 4630' & 4 SX CMT ON BOTTOM WITH DUMP BAILER. 1ST PLUG AT 1170' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4722	4732		
4680	4690		
4168	4172		
4138	4142		

INVOICED  
DATE 2/20/10  
INV. NO. 2010060823

RECEIVED  
DEC 14 2009  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED  
DEC - 7 2009  
KCC DODGE CITY

Signed Richard W. Lacey  
(TECHNICIAN)

Form CP-23