

\$ 165.10

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21635-00-00
Spot: N2N2SW Sec/Twnshp/Rge: 11-29S-19W
2310 feet from S Section Line, 1320 feet from W Section Line
Lease Name: UNRUH "C" Well #: 1-11
County: KIOWA Total Vertical Depth: 5080 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	646		WITH 325 SX CMT
PROD	4.5	5079	3275	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/03/2009 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2009 11:45 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 4900' WITH 4 SX CMT. 1ST PLUG AT 1260' WITH 15 SX GEL, WIPER PLUG, 100# HULLS & 50 SX CMT. 2ND PLUG PULL TO 680' & PUMP 100# HULLS & 50 SX CMT. 3RD PLUG PULL TO 300' & PUMP 40 SX CMT. 4TH PLUG PULL TO 40' & PUMP 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4950	4958		CHEROKEE LS

INVOICED
DATE 12/24/10
INV. NO. 2010060823

RECEIVED

DEC 15 2009

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed Jerry W. Stapleton
(TECHNICIAN)

RECEIVED
DEC 10 2009
KCC DODGE CITY

Form CP-22