

# 140.40

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21027-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 14-30S-9W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SWINGLE Well #: 1-14  
County: KINGMAN Total Vertical Depth: 4320 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	333		225 SXS CMT
PROD	4.5	4313	2035	250 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/19/2010 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4200', AND 4 SKS OF CMT. REC. CASING, 35 SKS 1350', 35 SKS, 900', CIRC 380'-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 01/19/2010 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4190', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2035 AND PULLED TO 1350', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 380', WHERE THE CMT WAS CIRC. TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4244	4264	CSG	

INVOICED  
DATE 2/26/10  
INV. NO. 2010060823

RECEIVED  
JAN 27 2010

Remarks: QUALITY OIL WELL CEMENTING #3986 60/40 4% GEL

Plugged through: CSG

KCC WICHITA

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

JK