

\$ 147.68

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-30268-00-00
Spot: S2NENW Sec/Twnshp/Rge: 12-30S-9W
4290 feet from S Section Line, 3300 feet from E Section Line
Lease Name: SWINGLE Well #: 2
County: KINGMAN Total Vertical Depth: 4544 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	283		
PROD	4.5	4500	2400	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2010 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND PERFS TO 4130 AND 4 SKS, 35 SKS 1350, 35 SKS 900 CIRC 330-0

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 01/19/2010 5:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4130 AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2400', AND PULLED TO 1350', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 330', WHERE CMT WAS CIRC'D TO SURFACE. PULLED REMAINING CASING.

Perfs:

INVOICED
DATE 2/26/10
INV. NO. 2010060823


RECEIVED
JAN 27 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING 3987 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

✓