

P 149.50

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20867-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 6-14S-32W
2215 feet from N Section Line, 2291 feet from W Section Line
Lease Name: BH HUCK TRUST Well #: 6-6
County: LOGAN Total Vertical Depth: 4600 feet

Operator License No.: 34056
Op Name: MAK-J ENERGY KANSAS LLC
Address: 1600 N BROADWAY, STE 1740
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	311	0	w/unknown sxs cmt

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/12/2010 12:45 PM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: _____ Company: MAK-J ENERGY KANSAS LLC Phone: (303) 468-0090

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel w/1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2010 4:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:
8 5/8" surface casing set at 311' w/unknown sxs cement.
TD at 4600'. Anhydrite 2357' - 2381'.
Circulated hole with heavy drilling mud.
Pulled drill pipe to 2365' - pumped 25 sxs cement.
Pulled drill pipe to 1248' - pumped 100 sxs cement.
Pulled drill pipe to 365' - pumped 40 sxs cement.
Pulled drill pipe to 40' - pumped 10 sxs cement.
Filled rathole to 5' from surface with 30 sxs cement.

Perfs:

INVOICED

DATE 2/26/10

INV. NO. 2010060827

RECEIVED
JAN 19 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #44453.

Plugged through: DP

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

JAN 13 2010