

98. 64

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20788-00-00
Spot: NENENE Sec/Twnshp/Rge: 23-33S-5E
4898 feet from S Section Line, 360 feet from E Section Line
Lease Name: ANDES Well #: 1
County: COWLEY Total Vertical Depth: 3035 feet

Operator License No.: 6875
Op Name: MARMIK OIL COMPANY
Address: 200 N JEFFERSON STE 500
EL DORADO, AR 71730

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208		
PROD	4.5	3015		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2009 12:00 PM
Plug Co. License No.: 30492 Plug Co. Name: NICHOLS WELL PULLING SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DARREN BROYLES Company: DRAKE EXPLORATION Phone: (620) 441-7223

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/30/2009 3:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
RIH ON WIRELINE, SET CIBP @ 2,970', DUMP BAILED 4 SXS CEMENT ON TOP. PRESSURED CASING @ 250#, HELD OK. PERFORATED SQUEEZE HOLES @ 300'-301'. SWEDGED INTO 4-1/2" CASING CONSOLIDATED OIL WELL ESTABLISHED CIRCULATION, AND MIXED AND PUMPED 125 SXS 60/40 POZ MIX 4% GEL TO SRUFACE. CEMENT CIRCULATED. PLUG DOWN 3:30 PM, 11-30-2009. CONSOLIDATED CEMENT TICKET #23820.

Perfs:

Top	Bot	Thru	Comments
3015	3035		OH

INVOICED
DATE 2/26/10
INV. NO. 2010060828

RECEIVED
DEC 29 2009
KCC WICHITA

Remarks: FORMERLY/PETROLEUM RESOURCES/STEPHENSON-SHAFER #1. GPS: LAT: 37.17048, LONG: 96.84360
Plugged through: TBG

District: 02 Signed Duane Krueger
(TECHNICIAN)

JK