

149.86

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20253-00-00
Spot: NWNESE Sec/Twnshp/Rge: 34-16S-29W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: LOHOFF A Well #: 1
County: LANE Total Vertical Depth: 4611 feet

Operator License No.: 32047
Op Name: MICA ENERGY CORP.
Address: P O BOX 20707
OKLAHOMA CITY, OK 73156

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4500		
SURF	8.625	324		WITH 225 SXC MT
PROD	4.5	4610	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2009 10:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN MONDERO Company: MICA ENERGY Phone: (785) 475-7245

Proposed Plugging Method: PUMP HULLS & 30 SX CMT AT 4200'. TEST CASING TO 300#. PERFORATE @ 1300'. PUMP CSAING VOLUME PLUS 80 SX CMT. PUMP 200 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2009 12:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 4134' & 4 SX CMT WITH BAILER. LOAD HOLE & PRESSURE TO 500#. HELD FOR 15 MINUTES. PERFORATE @ 1300'. PUMP 160 SX CMT @ 2-2 1/2 BBLS A MINUTE AT 400#. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 600#. PUMP DOWN BACKSIDE WITH 200 SX CMT. PUMP AT 150# & HELD POSITIVE PRESSURE.

Perfs:

Top	Bot	Thru	Comments
4469	4541		LWR MARM
4450	4454		PAWNEE
4384	4420		ALTAMONT
4357	4369		UPPER MARM.
4203	4214		LKC

INVOICED

DATE 2/26/10
INV. NO. 2010060832

RECEIVED

DEC 15 2009

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED

DEC 14 2009

KCC DODGE CITY

Signed

Jerry W. Stapleton
PIRTH

(TECHNICIAN)