

141.02

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21108-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 34-17S-25W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: REED Well #: 2
County: NESS Total Vertical Depth: 4339 feet

Operator License No.: 3925
Op Name: MISHLER, ROBERT DBA MISHLER OIL
Address: RT 1 PO BOX 78
RANSOM, KS 67572

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	332		WITH 195 SX CMT
DVT		1670		CEMENTED TO SURFACE
PROD	5.5	4320	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2009 8:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY D BRINEY Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS, THEN PULL TBG TO 1700' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2009 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4233' & PUMP 35 SX CMT THEN 150# HULLS. PULL TBG TO 1700' & PUMP 165 SX CMT. CMT CIRCULATED TO SURFACE. PULL TBG & TOP OFF WITH 40 SX CMT. TIE ONTO BACKSIDE & PUMP 50 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4325	4339	OH	

INVOICED
DATE 2/26/10
INV. NO 2010060834

RECEIVED
JAN 13 2010

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JAN 11 2010
KCC DODGE CITY

Form CP-2/3