

\$ 140.56

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21484-00-00
Spot: SESESW Sec/Twnshp/Rge: 34-17S-25W
276 feet from S Section Line, 2963 feet from E Section Line
Lease Name: REED Well #: 8
County: NESS Total Vertical Depth: 4325 feet

Operator License No.: 3925
Op Name: MISHLER, ROBERT DBA MISHLER OIL
Address: RT 1 PO BOX 78
RANSOM, KS 67572

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		WITH 4 SX CMT
SURF	8.625	362		CEMENTED TO SURFACE
PROD	5.5	4305	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2009 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: CIBP @ 4250' WITH 4 SX CMT. SET HOT PLUG @ 2130' WAIT UNTIL SET UP. TAG PLUG IF STAYS, PUMP 80 SX CMT OVER CASING VOLUME AT 1150' THEN 200 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2009 3:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

FOUND HOLES IN CASING @ 2090-2120' THEN 1120-1150'. SET CIBP @ 4250' WITH 4 SX CMT. RUN TBG TO 2150' & SPOT 50 SX COMMON CMT WITH 3% CC. WAIT 2 HOURS. TAG CMT AT 1997'. PULL TBG TO 1150' & PUMPED 100 SX CMT. DID NOT CIRCULATE. PULLED TBG & TIED ONTO CASING & PUMPED 200 SX CMT. MAXIMUM PRESSURE 200#. SHUT IN PRESSURE 50#. TIED ONTO BACKSIDE & PUMPED 35 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4305	4325	OH	

RECEIVED
DEC 31 2009
KCC WICHITA

INVOICED
DATE 2/26/10
INV. NO. 2010060834

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
DEC 29 2009
KCC DODGE CITY