

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19127-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 15-19S-4E
4875 feet from S Section Line, 4404 feet from E Section Line
Lease Name: THEIS A Well #: S
County: MARION Total Vertical Depth: 2318 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	0		
COND	15	0		
PROD	5.5	0	1250	

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/30/2009 8:00 AM

Plug Co. License No.: 30483 Plug Co. Name: KREMEIER, LES DBA KREMEIER PROD. AND OPER. CO.

Proposal Revd. from: Company: Phone: (785) 483-1307

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By:

WitnessType: PARTIAL

Date/Time Plugging Completed: 01/28/2010 12:45 PM

KCC Agent: SHANE JONES

Actual Plugging Report:

Perfs:

110/26/2009 I SPOKE TO TERRY MORRIS GLM PLANNING TO HAVE KREMEIER PLUG THE THEIS #5 AT THE END OF THE MONTH. 12/21/2009 KREMEIER MOVED IN AND SANDED OFF THE BOTTOM AND CAPPED WITH 5 SXS. 12/22/2009 KREMEIER SHOT OFF CASING @1250' AND WILL PULL UP TO 300' AND CIRCULATE CEMENT TO SURFACE. I FOUND OUT TODAY THAT TERRY MORRIS CP-1 SAID THERE WAS 15" CONDUCTOR PIPE IN THE HOLE. I TOLD KREMEIER WE HAD TO PLUG THE 15" ALSO, BUT NEEDED TO FIND IT FIRST. NO BACKHOE AVAILABLE AT THIS TIME. KREMEIER PULLED CASING AND RIGGED DOWN AND MOVED OFF. 1/12/2010 KREMEIER CALLED AND ASKED IF I WOULD GO BY AND CHECK THE THEIS A-5. THEY HAD DUG DOWN 10' PLUS AND FOUND NO CONDUCTOR PIPE. 1/28/2010 KREMEIER MOVED IN AND RAN 300' OF 2 7/8" TUBING IN THE HOLE. CONSOLIDATED TIED ON AND CIRCULATED 115 SXS TO SURFACE. KREMEIER PULLED THE TUBING AND CONSOLIDATED TOPPED OFF THE WELL W/15 SXS. PLUGGING COMPLETED AT 12:45 PM WITH 130 SXS OF 60/40 POS W/4% GEL TK #23262.

RECEIVED
FEB 12 2010

KCC WICHITA

INVOICED
DATE 2/26/10
INV. NO. 2010060837

Remarks:

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)