

#221

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20528-00-01
Spot: NESE Sec/Twnshp/Rge: 35-34S-35W
1983 feet from S Section Line, 677 feet from E Section Line
Lease Name: KINNEY CHESTER SAND UNI Well #: 1002W
County: STEVENS Total Vertical Depth: 6800 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2675		
SURF	8.625	1655		WITH 850 SX CMT
COND	20	40		WITH 4 1/5 YDS CMT
L1	2.875	6483	2611	TOC @ 2650
PROD	5.5	6785	1370	WITH 175 SX CMT

Well Type: EOR UIC Docket No: E27801.1 Date/Time to Plug: 01/05/2010 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 25 SX CMT @ STUB. 50 SX CMT AT 1700'+/-. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/08/2010 4:00 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

1ST PLUG SET CIBP @ 2675' INSIDE 2 7/8". PUMP 25 SX CMT AT 2600'. 2ND PLUG PUMP 25 SX CMT AT 1700' INSIDE 5 1/2". 3RD PLUG AT 1400' WITH 40 SX CMT. 4TH PLUG AT 600' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6545	6563		

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 25 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 3/01/10
INV. NO. 2010060847

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

RECEIVED
JAN 14 2010
KCC DODGE CITY

Signed Jack MacClaskey
(TECHNICIAN)