

\$ 182.5

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20979-00-00
Spot: SWNW Sec/Twnshp/Rge: 15-29S-34W
2130 feet from N Section Line, 510 feet from W Section Line
Lease Name: MLP PICKENS A Well #: 2
County: HASKELL Total Vertical Depth: 5600 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5310		
SURF	8.625	1770		WITH 675 SX CMT
PC		2973		WITH 450 SX CMT
PROD	5.5	5530	0	WITH 650 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2009 1:20 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2009 11:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PBTD 5310'. 1ST PLUG PUMPED 2 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. SHUT IN PRESSURE 500 PSI. 2ND PLUG PUMPED DOWN 5 1/2" CASING WITH 400# HULLS, 25 SX CMT, 70 BBL MUD SPACER, 25 SX CMT & THEN 20 BBL MUD SPACER & 80 SX CMT. CASING ON VACUUM. 3RD PLUG TAGGED TOC @ 785'. FILLED HOLE WITH MUD TO 600' & PUMP 20 SX CMT. 4TH PLUG FILLED HOLE WITH MUD TO 80' & PUMPED 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5468	5472		
5430	5450		
5270	5272		
5232	5238		

RECEIVED
JAN 04 2010
KCC WICHITA

INVOICED

Remarks: USED COMMON CEMENT BY SARGENTS.

DATE 3/01/10
INV. NO. 2010060847

Plugged through: CSG

District: 01

Signed Jerry W. Stapleton
(TECHNICIAN)
PIRT II

RECEIVED
DEC 29 2009

KCC DODGE CITY

Form CP-23