

186.06

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21585-00-02
Spot: E2NWNENE Sec/Twnshp/Rge: 5-31S-34W
330 feet from N Section Line, 880 feet from E Section Line
Lease Name: MLP YOUNG TRUST B Well #: 2
County: SEWARD Total Vertical Depth: 5725 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4050 | | WITH 2 SX CMT |
| CIBP | | 5400 | | W/ 2 SX CMT |
| SURF | 8.625 | 1607 | | WITH 800 SX CMT |
| PC | | 3028 | | WITH 300 SX CMT |
| PROD | 5.5 | 5725 | 0 | WITH 625 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/14/2009 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1620' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40 WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2009 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 4050' WITH 2 SX CMT. 1ST PLUG AT 1780' WITH 35 SX CMT. 2ND PLUG AT 600' WITH 70 SX CMT. FILLED TO SURFACE. PUMP 5 SX CMT DOWN 5 1/2' X 8 5/8" ANNULUS. PRESSURED TO 300#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5543 | 5545 | | |
| 5490 | 5500 | | |
| 5480 | 5484 | | |
| 5460 | 5464 | | |
| 4808 | 4814 | | |
| 4679 | 4683 | | |

RECEIVED
DEC 18 2009
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

INVOICED
DATE 3/2/10
INV. NO. 2010060847

District: 01

RECEIVED
DEC 15 2009
KCC DODGE CITY

Signed Jack Macloskey
(TECHNICIAN)