

\$ 177.71

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20257-00-02
Spot: SWNW Sec/Twnshp/Rge: 7-29S-33W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: UNRUH B Well #: 3
County: HASKELL Total Vertical Depth: 5468 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2475		WITH 2 SX CMT
CIBP		2730		
SURF	8.625	1820		WITH 825 SX CMT
COND	21	40		WITH 4 YDS CMT
PROD	5.5	5459	1401	WITH 140 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/17/2009 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JAY Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: 50 SX CMT AT STUB. PLUG AT 700' WITH 40 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2009 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2475' WITH 2 SX CMT. 1ST PLUG AT 1370' WITH 50 SX CMT. 2ND PLUG AT 702' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5328	5336		
2816	2817		
2790	2791		
2670	2674		
2650	2651		
2616	2620		
2582	2586		
2554	2558		
2530	2531		

INVOICED
DATE 3/01/10
INV. NO. 2010060847
RECEIVED
JAN 07 2010

Remarks: USED COMMON CEMENT BY SARGENTS.
Plugged through: CSG

KCC WICHITA

District: 01

RECEIVED

DEC 18 2009

KCC DODGE CITY

Signed

(TECHNICIAN)