

123.60

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03224-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 33-10S-23W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: DIEBOLT B Well #: 5
County: GRAHAM Total Vertical Depth: 3803 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	227	0	175 SX CMT
PROD	5.5	3803	0	125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/08/2010 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed	02/08/2010 - Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plugging	02/09/2010 - Ordered 210 sxs 60/40 pozmix - 4% gel - 350# hulls.
Method:	Perfed at 1090'. Fish, tubing and rods stuck in the hole at 1546'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2010 11:15 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

<p>02/08/2010 - Ran tubing to 1386'. Tubing tried to stick in the hole. Pumped 50 sxs 60/40 pozmix - 4% gel. Pulled tubing to 1058' - pumped 250 sxs 60/40 pozmix - 4% gel with 500# hulls. Pulled all tubing - let well set overnight. 02/09/2010 - Ran tubing in the hole and tagged cement at 972'. Pulled tubing up to 962' - pumped 85 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface. Pulled all tubing. Topped off 5 1/2" casing with 10 sxs 60/40 pozmix - 4% gel. Hooked to 8 5/8" x 5 1/2" annulus. Pumped 115 sxs 60/40 pozmix - 4% gel with 150# hulls. S.I.P. 100#.</p>	
---	--

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 16 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 2/24/10
INV. NO. 2010060839

Remarks: ALLIED CEMENTING COMPANY-TICKET #33808 AND #39189.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

IMPERIAL OIL

#5 DIEBOLT

33-10-23W
NW NW NE

Contr. SCHAFFER DRLG GRAHAM County

E 2368 Comm. Comp. 8-19-55 IP 265 BOPD

Tops	Depth	Datum
HEEB	3571	=1203
LANS	3606	=1238
TD	3803	=1435

Casing
 8" 227
 5" 3803
 DST 3600-12/1 HR, 504' SW,
 BHP 1070#
 DST 3768-82/1 HR, 660' GAS,
 63' HQ & GCM, BHP 670#
 PERF 30/3773-77: BAIL 5
 GOPH: ACID 500: SWB 19 BOPH/
 8 HR:
 DIEBOLT POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS