

\$123.27

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03225-00-02
Spot: SEWNWE Sec/Twnshp/Rge: 33-10S-23W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DIEBOLT B Well #: 6
County: GRAHAM Total Vertical Depth: 3793 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225	0	w/unknown sxs cmt
PROD	5.5	3793	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2010 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.
CIBP at 3630'. Shoot perms at 2250' - 1380' - 1090'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2010 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3504' - pumped 115 sxs cement with 250# hulls.
Pulled tubing to 2255' - pumped 106 sxs cement w/150# hulls.
Pulled tubing to 1099' - pumped 85 sxs cement with 100# hulls - pulled tubing out.
Tied onto backside - squeezed - pumped 50 sxs cement with 100# hulls.
Shut in at 150# P.S.I.
Filled 5 1/2" down top with 30 sxs cement - full.

Perfs:

Top	Bot	Thru	Comments
3587	3589		
3532	3535		

INVOICED
DATE 2/26/10
INV. NO. 2010060839

RECEIVED
FEB 12 2010

Remarks: ALLIED CEMENTING COMPANY-TICKET #44474.

KCC WICHITA

Plugged through: TBG

District: 04

Signed CM Mills
(TECHNICIAN) CM

FEB 03 2010

IMPERIAL OIL

#6 DIEBOLT

33-10-23W
SE NW NE

Contr. SCHAFFER DRLG

GRAHAM

County

E. 2367RB

Comm.

Comp. 9-16-55

IP 706-BOPD

Tops	Depth	Datum
ANH	1370	997
HEEB	3563	-1196
LANS	3600	-1233
TD	3793	-1426

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing

8" 225

5" 3793

DST 3592-3606/1 HR, 120'

GAS; 90' OCM, 360' WTR;

BHP 890#

DST. 3756-72/45", 1800' OI L

BHP 600; DST: 3774-93/1 HR

90' GAS & OCM, BHP 205#

DIEBOLT POOL 30/3762-67

2000' OIH/45"

ACID 1000; SWB

25-BOPH/4 HR

+	+	+
+	+	+
+	+	+