

\$ 104.00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-08535-00-00  
Spot: S2SEW Sec/Twnshp/Rge: 8-15S-13W  
2970 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: REIN GEORGE JR Well #: 4  
County: RUSSELL Total Vertical Depth: 3200 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	266	0	w/80 sxs cmt
PROD	5.5	3188	0	w/140 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/28/2009 2:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: MARK ROBBIN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method:	Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls. Junk in the hole at 2893' - tubing stacked out at 960'. Casing probably parted. 1966 - Squeezed 325'-330' w/400 sxs; 1543'-1573' w/unknown sxs. Ordered an additional 250 sxs 60/40 pozmix - 4% gel - 300# hulls.
---------------------------	--

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/30/2009 10:00 AM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing to 960' - pumped 250 sxs cement with 300# hulls - no circulation. Needed to order more cement - ran out.  
Pumped 85 sxs cement with 300# hulls - good circulation of cement.  
Pulled tubing out - pumped 45 sxs down - top still dropping - stopped at 206'.  
Tied onto backside - pumped 5 sxs cement - full - shut in 200# P.S.I.  
Redimix down the top with 25 sxs cement - casing was full.

Perfs: \_\_\_\_\_  
  
RECEIVED  
JAN 06 2010  
KCC WICHITA

INVOICED  
DATE 2/26/10  
INV. NO. 2010060839

Remarks: ALLIED CEMENTING COMPANY-TICKET #33686.  
Plugged through: TBG

District: 04 Signed Marvin Mills  
(TECHNICIAN) CM

JAN 04 2010

SKELLY OIL CO.

GEO. REYN JR

8-15-13W

CSL SE NW

Contr.

RUSSELL

County

E 1746 Comm 9-11-39 Comp 10-4-39 IP 910 BOPD ECHO

Tops	Depth	Datum
LANS	2909	
ARB	3185 or 3190	
TD	3200 $\frac{1}{2}$	

Casing  
5" 3188

A/500  
SO 2929-49


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS