

3-31
4-031677 15-065-20886-00-00

42
K

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-20,886
NE SW NW /4 SEC. 20, 10 S, 24 W
3630 feet from S section line
4290 feet from E section line

Operator license# 9067 Lease D. Rush well # A-4

Operator: DaMar Resources, Inc. County Graham

Address: Box 70 Well total depth 3985 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 246 feet

129.51

Aband. oil well , Gas well , Input well , SWD , D & A WSW

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 31 Month: March Year: 92

Plugging proposal received from: Curt Longpine

Company: DaMar Resources, Inc. Phone: _____

Were: Order 350 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Shots @ 1221' - 2050'. Hole open to produce perfs by Wireline.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 3:00P.M., Day: 31, Month: March, Year: 92

Actual plugging report: 8 5/8" set @ 246' with 175 sx. 4 1/2" set @
3984' with 235 sx. 3946 P.B.T.D. Perf's @ 3607' - 3921'. Squeeze
8 5/8" w/100 sx. cement blend to max. P.S.I. 500#. Close in P.S.I. 500#.
Squeezed 4 1/2" w/250 sx. cement blend w/500# hulls mixed in to max.
P.S.I. 600#. Close in P.S.I. 350#. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy.plug: YES 2050 NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2416 GL

I did not [] observe the plugging. Carl Goodrow

DATE 4-22-92
INV. NO. 34969

(agent)
Form CP-2/3

Rec'd
4-9-92
4-9-92