

6 031435

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-20,087

NW NW NW, SEC. 20, T 10 S, R 24 W/E

4950 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3135

Lease Name Gay Rush Well # B-3

Operator: Crump Pet Corp

County Graham 130.00

Name & Address 710 N. Colorado Suite 115

Well Total Depth 4000 feet

box 1732

Conductor Pipe: Size feet

Midland, Tx. 79701

Surface Casing: Size 8 5/8 feet 179

Abandoned Oil Well xx Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling License Number 6033

Address Hill City, Ks.

Company to plug at: Hour: PM Day: 19 Month: Sept Year: 19 90

Plugging proposal received from Mike bob Bocell

(company name) Murfin Crump (phone)

were: 8 5/8 set at 179 w/150 sks cwc. 5 1/2 set at 3999. Ordered 400 sks

65/35 poz 8% gel 500 lbs. hulls. Allied Cement Co. Murfin Water Trucks.

Perf at 2050 anhy - 1225 Kiowa. Hole open to prod. Perfs. fluid low in hole

fish at 3895. Below top perf.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part xx None

Operations Completed: Hour: 12:30 PM Day: 19 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sq 5 1/2 w/50 sks cement blend straight followed by

250 sks cement blend w/400 lbs. hulls mixed into max psi 700 lbs.

Close in psi 400 lbs. Sq 8 5/8 w/100 sks cement blend w/100 sks hulls mixed into

max psi 500 lbs. Close in psi 100 lbs. Plug complete.

Remarks:

RECEIVED STATE CORPORATION COMMISSION

(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

OCT 17 1990

10-17-1990
CONSERVATION DIVISION
Wichita, Kansas
Carl Goodrow

Carl Goodrow (TECHNICIAN)

DATE 10-18-90

INV. NO. 29629

9-19