

6 030402

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-22,147

S45W N4W SEC. 4, T 10 S, R 25 W E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Operator: John O Farmer Inc.

Name & Address P.O. Box 352

Russell, Kansas

67665

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor John O Farmer License Number 220

Address as above

Company to plug at: Hour: AM Day: 25 Month: 3 Year: 19 85

Plugging proposal received from Herman Mick

(company name) John O. Farmer (phone) \_\_\_\_\_

were: 8 5/8 set @ 260' w/ 170 sp. Order 190 sp 50/50 ppg 6 bag 3 pcc 8 5/8 w.p.  
Circulate hole with no less than 36 Uvis mud and maintain  
mud level at surface.

Allied Cement. Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9 AM Day: 25 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Spot O.P. @ 2230' Displace 25 sp Cement. lay down  
O.P. to 1300' displace 100 sp Cement. lay down O.P. to 275'  
displace 40 sp. cement. lay down O.P. Push W.P. to 40'  
fill hole with cement to base of collar. Displace 15 sp  
Cement in rat hole. Plugging Complete

RECEIVED  
STATE CORPORATION COMMISSION  
4-5-1985  
APR 05 1985

Remarks: Elev. 2558 July 2200-45

(If additional description is necessary, use BACK CONSERVATION DIVISION FORM # 107 m.)  
Wichita, Kansas

INVOICED (I did / did not) observe this plugging.

DATE 4-9-85

INV. NO. 7529

Signed Carl Goodrow (TECHNICIAN) 4-3-85  
34