

To: **STATE CORPORATION COMMISSION**
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E 16, 842 065-20,009

TECHNICIAN'S PLUGGING REPORT

Operator License # 03135

Operator: Crump Petroleum Corp
Name & Address: 710 North Colorado Suite 115
Box 1732
Midland, Texas 79701

NE NE NW, SEC. 20, T. 10 S, R. 24 W/E
4950 feet from S section line

2970 feet from E section line

Lease Name Rush B Well # 2

County Graham 130.33

Well Total Depth 4010 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 187

Abandoned Oil Well _____ Gas Well _____ Input Well xx SWD Well _____ D&A _____

Other well as hereinafter indicated E 16,842

Plugging Contractor Murfin License Number 6033

Address Hill City, Ks.

Company to plug at: Hour: PM Day: 22 Month: Jan Year: 19 90

Plugging proposal received from John Gerstner

(company name) Murfin (phone) _____

were: 8 5/8" set at 187 w/150 sks. 4 1/2" set at 4009' w/150 sks. Zone of perf

top 3792' - 3979'. Actual perf 3936 - 42 KC. Packer and tubing stuck in hole. Fish at 1422'

Move in rig over hole. Free point and back off at 2308'. Well sanded in. Order 300 sks

35/65 poz 8% gel 400# hulls. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part xx None _____

Operations Completed: Hour: 3:30PM Day: 22 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 2300' circ cement blend to surface w/145 sks.

Lay down tubing, squeezed 4 1/2" w/total of 175 sks cement blend w/400# hulls to max psi
300#. Close in 300#. Backside squeezed w/125 sks to max psi 300#. Close in 150#.

Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
2-14-1990

FEB 14 1990

Remarks: Anhy 2075 - 2110 Dakota.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging. Wichita, Kansas

INVOICED

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow

DATE 2-15-90
INV. NO. 27447