

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-19002-00-00<sup>01</sup>  
Spot: NWSWNE Sec/Twnshp/Rge: 6-10S-25W  
3630 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: GRASHER BRUNGARDT Well Number: B-2  
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/2  
Surface Casing: Size 8.62 feet: 198 125 SX CMT  
Production: Size 4.5 feet: 4050 600 SX CMT  
Liner: Size feet:

Well Type: EOR UIC Docket No: E21996.4 Date/Time to Plug: 01/29/2002 11:00 AM

Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.

Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 355 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Perfs 3915' - 3917'; 3924' - 3926'.  
Squeezed at 1962' - 1993' with 400 sxs.  
Junk in the hole.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/29/2002 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Berexco RIH with tubing to 3557' - spotted 60 sxs 60/40 pozmix with 250# hulls.  
Pulled tubing to 2241' - pumped 125 sxs 60/40 pozmix with 250# hulls until cement circulated.  
Pulled tubing - tied onto casing with a swedge and pumped 20 sxs 60/40 pozmix with Max. P.S.I. 700#. S.I.P. 200#.  
Tied onto backside and pumped 120 sxs into backside.  
Backside did not pressure up.

RECEIVED  
2-4-2002  
FEB - 4 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY - TICKET #9188.

Plugged through: TBG

District: 04

Signed

*Patrick Staab*  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE Feb 6-02

INV. NO. 2002061347

JAN 30 2002

BEREXCO INC  
WICHITA KS 67202

6-10 -25W  
NW SW NE

#B-2 GRA-SHER QWWO

site: 1-3/4 N & 3-1/2 W OF ST PETER KS      cty: GRAHAM      API IOG-20444  
 contr: UNKNOWN      field: GRA-SHER  
 geol:  
 date 07/15/91      spd date 12/05/90      drig comp 12/05/90      card issued 07/15/91      last revised 07/15/91


ELV: 2588 KB SMP	
tops.....	depth/datum
HEEB.....	3808 -1220
TOR.....	3828 -1240
KC.....	3835 -1247
PBTD.....	3922 -1334
RTD OLD.....	4050 -1462

IP status:  
 SWDW, LKC 3915-3917,  
 OLD INFO: OPERATOR WAS KIMBARK OIL & GAS, 2  
 BRUNGARDT, SPD 03/16/59 , 03/23/59 SET 8-5/8" 198,  
 5-1/2" 4050, DV TOOL AT 1993 / 700 SX, ABD OIL, P 84  
 BOPD, LKC 3915-3917 , (CARD ISSUED 04/24/59 )  
 CONTR: LOGAN DRILLING  
 GEOL: RALPH RUWWE  
 NO CORES OR DSTS  
 MICT - CO, (LKC OH), HFW, PB (DEPTH NA), PF (LKC)  
 3924-3926, REC WTR, SQZ'D PFS, PF (LKC) 3915-3917,  
 AC 2500 GAL, SWB 10 BOPH, POP, P 84 BOPD  
 NEW INFO: FR 07/15/91 , REWORKED 12/05/90 DC  
 12/05/90

COPYRIGHT 1990  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

(over)

BEREXCO INC  
WICHITA KS 67202

6-10 -25W  
NW SW NE

#B-2 GRA-SHER QWWO

ELEV ON REWORK WAS 2589 KB; 2584 GL  
 MICT - CO, SQZ'D PFS (3924-3926) W / 100 SX CMT, CO CMT, SET CIBP AT 4030, PB 3922 TD,  
 PF (LKC) 3915-3917, W / 6 SPF, AC 500 GAL, SWDW - INJECTION RATE SATISFACTORY 1/7/91

KIMBARK COMPANY

#2 BRUNGARDT

6-10-25W  
NW SW NE

Contr. LOGAN DRLG      GRAHAM County

E 2588RE Comm. 3-16-59      Comp. 4-24-59      IP 84 BOPD  
 PHY POT

Tops	Depth	Datum
HEEB	3808	-1220
TOR	3828	-1240
KC	3835	-1247
TD	4050	-1462

Casing  
 8" 190  
 5" 4050  
 CO: HFW: PB: PERF 3924-26: WTR:  
 SQZ: PERF 3915-17: ACID 2500:  
 10 BOPH

GRA-SHER POOL


(RALPH RUWWE, GEO.)

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS