

5-4-88 15-065-01903-00-00

6 031086

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NW NW SE, SEC. 6, T 10 S, R 25 W

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Graff Well # 1

Operator: Berexco Inc.

County Graham 13/17

Name & Address 970 Fourth Financial Center

Well Total Depth 4036 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 189

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Hays, Ks.

Company to plug at: Hour: PM Day: 4 Month: May Year: 19 88

Plugging proposal received from Bob Grant

(company name) Berexco (phone)

were: 8 5/8" set at 189' cwc. 4 1/2" set at 4043' cement, N.A. PBD 3993'.

Perf 3868' - 4022'. Order 50 sks Common Cement 250 sks Cement Blend. 5 sks Hulls.

B. J. Titan Cement Co. Wellbrock Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:30PM Day: 4 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to 3269'. Pumped 25 sks Cement Blend followed w/36 BBLs (80 sks) Cement Blend w/4 sks Hulls mixed in. Followed w/50 sks Common Cement w/1 sk Hulls mixed in. Lay down tubing. Squeeze 4 1/2". To max Psi 600#. Close in Psi 300#. Checked annulus to 500# w/1/2 Bbl cement. Close in Psi 300#. Held. Plug complete.

RECEIVED STATE CORPORATION COMMISSION 7-6-1988 JUL 6 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.)

DATE 7-7-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 21197