

15-065-01904-00-00  
4-3

41  
R

4-031678

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1959  
NW NE SE /4 SEC. 06 , 10 S, 25 W  
2310 feet from S section line  
990 feet from E section line

Operator license# 5363 Lease Grasher well # GR-2

Operator: Berexco, Inc. County Graham

Address: Box 723 Well total depth 4005 feet <sup>130.16</sup>  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 200 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: B.J. Services License#    

Address: Oakley, Kansas

Company to plug at: Hour: A.M. Day: 3 Month: April Year: 92

Plugging proposal received from: George Jorgensen

Company: Berexco, Inc. Phone:    

Were: Order 350 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Well squeezed 1536' w/200 sx. 2900' - 3540'-3220' w/300 sx. Other bottom  
hole squeezed. Cement was showing in braden head.  
Shot @ 1300' Kiowa. Hole dry to produce perfs. By Wireline.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 12:00P.M., Day: 3, Month: April, Year: 92

Actual plugging report: 8 5/8" set @ 200' with 125 sx. 4 1/2" set @  
4004' w/50 sx. plus 600 gal. latex. D.V. tool @ 2059' circulate with 100  
BBL. Kim pack oil base mud.  
Squeezed 8 5/8" with 1/2 BBL slurry to 500#. Locked up. Released  
pressure. Squeezed 4 1/2" with 200 sx. cement blend w/500# hulls mixed  
in to max. P.S.I. 500#. Close in P.S.I. 350#. Plug complete.

Remarks:      
Condition of casing(in hole): GOOD     BAD X Anhy.plug: YES 1950 NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation: 2545 GL    

I did X did not     observe the plugging. Carl Goodrow

INVOICED  
DATE 4-27-92  
INV. NO. 35064

(agent)  
Form CP-2/3

*Doc*  
*4-9-92*