

15-015-40094-00-00
2 030512
6-5-87

20 R

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 8-1917
NW NW NE SEC. 23, T 25 S, R 6 ~~XWF~~
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name Clayton-Platt Well # 1

Operator: State Of Kansas
Name &
Address 200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286

County Butler
Well Total Depth 2900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size No casing in hole feet

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated Well drilled as dry but not plugged

Plugging Contractor McPherson Drilling Company License Number 5495

Address R.R. #2, Box 168-D, Augusta, KS 67010

Company to plug at: Hour: 10:00am Day: 2 Month: 6 Year: 1987

Plugging proposal received from _____
(company name) _____ (phone) _____

were: Set 20' conductor casing--clean hole to 200'+-- cement hole to surface

15 1/2" casing 120' 12 1/2" casing 615' 10" casing 1476' 8 1/4" casing 1647' 6 5/8" casing
2370' All Casing Pulled

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:15 Day: 5 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 6/2/87 Ran 13' of 20" casing with poor boy packed, Lewis & West, #6578, dumped 2 yards sand-mix outside 20" to surface, let set. 6/4/87 Circulate and drill hole 15" to 213', pulled d.p. and bit, ran d.p. to 213' United Cementing spotted 50 sx C.A.2% cc, pulled d.p. 6/5/87 Ran d.p. to top of cement (185'), United Cementing pumped. 292 sx 60-40 pozmix, 6% gel to surface, pulled d.p., filled hole to surface.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED (If applicable) observe this plugging.

JUN 6 - 1987
CONSERVATION DIVISION
Wichita, Kansas
Signed Don Thompson
(TECHNICIAN)

DATE _____

INV. NO. _____