

2030199

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 12-10-1939

NE, SEC. 4, T 26 S, R 5 NE

4196' feet from W/S section line

1941' feet from NE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Millheiser A Well # 2-A

Operator: Cities Service Oil & Gas Corp

County Butler 86.19

Name & Address 800 Sutton Place Bldg.

Well Total Depth 2652' feet

209 E. William

~~6~~ Pipe: Size 7" feet 2611

Wichita, Ks. 67202

~~5~~ Casing: Size 5 1/2" feet 2595'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor United Oil Well Cementing & Acid License Number _____

Address Box 712, Eldorado, Ks. 67042

Company to plug at: Hour: 09:30 Day: 25 Month: 3 Year: 1985

Plugging proposal received from Steve Darwin

(company name) Cities Service Oil & Gas Corp. (phone) _____

were: Run 2 3/8" tub to 2500', spot 50% cement, pull tub, let set.
run 1" to top of cement, perf. casing below 300', pump cement
down 5 1/2" csg. to surface, leave 5 1/2" csg full of cement.

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 17:00 Day: 25 Month: 3 Year: 1985

ACTUAL PLUGGING REPORT Washed 2 3/8" tub to 570' could not go further.

Pulled tub, ran 1" outside 7" csg. to 315', United Cementing #11972
pumped 4 cu gal, 325 cu cent. 3% cc. to surface, pulled 1".

ran 2 3/8" tub inside 5 1/2" csg. to 420', pumped 135 cu cent
3% c.c. to surface, pulled tub. filled csg. with cement.

Remarks: Perf. 2504' - Miss 2590' - Viola Question about whether csg.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-15-85

INV. NO. 7722

W

Signed Don Thompson
(TECHNICIAN)

APR 09 1985

PO