

2-050762

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

10-22

KCC CONTROL # 970179-001

DOCKET # ~~D-18,350~~ D-18580

API NUMBER: 15-035-20,267-00-00

NE SE NE , SECTION 28 TOWNSHIP 31 RANGE 5E

OPERATOR LICENSE # 100 3390 FEET FROM S SECTION LINE

OPERATOR KANSAS CORPORATION COMMISSION 315 FEET FROM E SECTION LINE

NAME & 130 SOUTH MARKET #2125

ADDRESS WICHITA, KS 67202

LEASE NAME: NICHOLS-GRAIG #1

COUNTY: COWLEY

WELL TOTAL DEPTH: 2370'

PIPE: 4 1/2" @ 2370'

SURFACE CASING: 8 5/8" @ 138'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD X D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: B & S WELL SERVICE

ADDRESS: 608 WEST EIGHTH STREET, WINFIELD, KS 67156 LICENSE: 6013

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 21 MONTH: 10 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT II

COMPANY NAME: UNITED CEMENTING PHONE: (316) 321-4680

WERE: DIG OUT WELLHEAD, CELLAR, AND PIT. RIG UP PULLING UNIT. SAND BACK AND SPOT 5 SACKS OF CEMENT AT 1890'. RUN 1" PIPE DOWN ANNULUS AND INSIDE CASING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL PIPE OUT OF HOLE AND TOP OFF WITH CEMENT. CUT OFF CASING, CLOSE PIT, REMEDIATE SURFACE DAMAGE.

PLUGGING PROPOSAL RECEIVED BY: DALE SMITH

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( X ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 16:00 DAY: 22 MONTH: 10 YEAR: 1997

ACTUAL PLUGGING REPORT: DUG OUT WELLHEAD, CELLAR, AND PIT. RIGGED UP PULLING UNIT. RAN BAILER TO 580' AND HIT SOLID. HAULED TUBING TO LOCATION. RAN TUBING AND BIT TO 580' AND WASHED DOWN TO 600'. WASHED AND DRILLED AT 600'. WOULD NOT DRILL DOWN. CIRCULATED CEMENT INSIDE 4 1/2" CASING FROM 600' TO SURFACE. PULLED TUBING OUT OF CASING. TOPPED OFF CASING WITH CEMENT. RAN 1" PIPE DOWN ANNULUS TO 15' AND CEMENTED TO SURFACE. EMPTIED PIT. CLOSED PIT CUT OFF CASING. REMEDIATED SURFACE DAMAGE.

REMARKS: 60/40 POZ 4% GEL 90 SACKS CEMENT UNITED #4594

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 10 1997

CONSERVATION DIVISION  
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

JERRY CLARK