

187. 10

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21172-00-00
Spot: NWNW Sec/Twnshp/Rge: 22-31S-33W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: FORT HAYS STATE Well #: 1-22
County: SEWARD Total Vertical Depth: 5757 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5502		WITH 2 SX CMT
SURF	8.625	1809		WITH 800 SX CMT
DVT		2992		WITH 450 SX CMT
PROD	5.5	5745	0	WITH 265 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/06/2010 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: FRED CRESS Company: PRESCO WESTERN Phone: (303) 444-8881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2010 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 5502' & 2 SX CMT. 2ND PLUG TEST 5 1/2" CASING TO 350#. PERFORATE 5 1/2" @ 1830'. PRESSURED TO 1000#. 3RD PLUG RAN BOND LOG. TOC @ 790'. RAN CASING SWAB TO 1830'. PUMPED 75 SX CMT & DISPLACED WITH 24 BBL WATER. 4TH PLUG PERFORATE 5 1/2" @ 650'. CIRCULATE CMT TO SURFACE WITH 150 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5553	5558		CHESTER

INVOICED
DATE 3/08/10
INV. NO. 2010060853

RECEIVED
FEB 08 2010
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED
JAN 15 2010
KCC DODGE CITY

Signed Ken Jehlik
(TECHNICIAN)