

\$182.03

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20161-00-00  
Spot: NWSE Sec/Twnshp/Rge: 28-29S-33W  
1920 feet from S Section Line, 1922 feet from E Section Line  
Lease Name: HALL - SG Well #: 2  
County: HASKELL Total Vertical Depth: 5601 feet

Operator License No.: 32309  
Op Name: PRESCO WESTERN LLC  
Address: 5665 FLATIRON PKWY  
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3600		WITH 5 SX CMT
CIBP		4650		WITH 5 SX CMT
CIBP		4864		
CIBP		5350		
SURF	9.625	1628		WITH 650 SX CMT
PROD	7	5600	0	WITH 400 SX CMT
RBP		4754		WITH 10 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2009 10:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: FRESS CROSS Company: PRESCO WESTERN Phone: (303) 444-8881

Proposed Plugging Method: RBP @ 4754'. PLUG AT 4750' WITH 10 SX CMT. SET CIBP @ 4650' & 10 SX CMT. TEST CASING TO 300#. PERFORATE @ 1640' & CIRCULATE CMT TO SURFACE

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/21/2009 7:30 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

1ST PLUG CIBP @ 4650' WITH 5 SX CMT. TESTED 7" CASING TO 300#. NEVER HELD. BLED OFF 100-150# IN 1 MINUTE. 2ND PLUG SET CIBP @ 3600' WITH 5 SX CMT. TESTED CASING TO 300#. 3RD PLUG PERFORATE 7" @ 1640'. PUMP 475 SX CMT & CIRCULATE CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5407	5410		CHESTER
5360	5366		CHESTER
5340	5344		MORROW
5330	5334		MORROW
5277	5281		MORROW
4892	4898		MARMATON
4800	4812		MARMATON
4666	4670		KANSAS CITY B
4618	4626		KANSAS CITY A
4338	4350		LANSING F
4270	4276		LANSING D
4225	4234		LANSING B

RECEIVED  
JAN 19 2010

INVOICE KCC WICHITA

DATE 3/03/10  
INV. NO. 2010060853

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED  
DEC 29 2009

Signed

*Jack MacClaskey*  
(TECHNICIAN)

KCC DODGE CITY