

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-35097-00-00
Spot: N2SWSW Sec/Twnshp/Rge: 7-17S-9W
921 feet from S Section Line, 4822 feet from E Section Line
Lease Name: MUSENBERG C Well #: 1
County: ELLSWORTH Total Vertical Depth: 3232 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 1105 WALNUT
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	241		175 SXS
PROD	5.5	3230		175 SXS

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2010 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DIXON Company: DS & W WELL SERVICING INC Phone: (620) 786-4258

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 02/23/2010 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. ON 2-22-2010, RAN TUBING TO 2440' AND PUMP 35 SX'S THIXOTROPIC CEMENT, PULL TUBING TO 1050', LET SET FOR 1 HR. RAN TUBING BACK DOWN TO 2440, COULD NOT TAG CEMENT. PUMP 50-60 MORE SX'S CEMENT, PULL TUBING TO 1050' AND SHUT DOWN FOR DAY. CAME BACK ON 2-23-2010 AND TAGGED CEMENT AT 1150' WITH WIRELINE. PUMP 35 SXS CEMENT @ 1050' WITH 200#'S PRESSURE-HAD CIRCULATION. PULL TUBING TO 700' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 300' AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON CASING AND CIRCULATED CEMENT UP BACKSIDE OF CASING. PULL TUBING OUT AND TOP OFF. USED 260 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3085	3087	CSG	
2992	2998	CSG	
2926	2930	CSG	
2490	2492	CSG	

INVOICED
DATE 3/25/10
INV. NO. 2010060907

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 08 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. LOG TECH TICKET #29517. COPELAND TICKET #C-35823 GPS: LAT: 38.58226, LONG: 98.36681

Plugged through: TBG

District: 02

Signed Jeff Klock DISTRICT SUPERVISOR
(TECHNICIAN)