

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-01229-00-00
Spot: NWSW Sec/Twnshp/Rge: 25-19S-2W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: UNRUH B Well #: 1
County: MCPHERSON Total Vertical Depth: 2958 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13	670		CIRCULATED
COND	4.5	2850		CIRCULATED
PROD	5.5	2912		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/03/2010 10:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE Phone: (620) 628-4723

Proposed Plugging Method: SAND TO 2862' AND CAP W/5 SXS CEMENT. PUMP FROM 450' INSIDE CASING TO CIRCULATE TO SURFACE. PUMP FROM 450' BETWEEN 5 1/2" AND 13" AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 03/04/2010 9:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2820' AND CAPPED WITH 5 SXS CEMENT. RAN 2" TUBING ON THE BACKSIDE OF 5 1/2" CASING AND TAGGED CEMENT AT 320'. PUMPED 320 SXS CEMENT W/CALCIUM CHLORIDE BETWEEN THE 5 1/2" CASING AND 13" SURFACE PIPE. PLUG CIRCULATED BUT DID NOT GET CEMENT TO SURFACE. RAN TUBING TO 400' INSIDE 5 1/2" CASING AND PUMPED 50 SXS CEMENT WITH 2 SACKS OF COTTONSEED HULLS TO FILL TO SURFACE. RAN TUBING BACK DOWN BACKSIDE TO 320' AND PUMPED 270 SXS CEMENT WITH CALCIUM CHLORIDE. RETURNED THE NEXT DAY AND TAGGED CEMENT AT 60' IN 5 1/2" CASING AND ALSO 60' ON BACKSIDE. PUMPED 10 SXS CEMENT IN 5 1/2" CASING TO CIRCULATE TO SURFACE. PUMPED 105 SXS ON THE BACKSIDE TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2912	2958	TBG	

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 12 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 3/25/10
INV. NO. 2010060970

Remarks: COPELAND CEMENTING TICKET #34461 640 & 115 TOTAL = 755 SXS. 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

JK