

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20694-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 25-10S-24W
440 feet from N Section Line, 1090 feet from E Section Line
Lease Name: MABELLE Well #: 1
County: GRAHAM Total Vertical Depth: 4020 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	174	0	150 SX
PROD	5.5	4014	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2010 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.
No records above salt section. Perforate anhy and base Dakota.
Old squeeze jobs: 3177'-3209' w/100 sxs; 2866'-2897' w/250 sxs.
Bad pipe: 2500' - 2795'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2010 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 2023' and 1200'.
Ran tubing to 2798' - pumped 50 sxs cement with 200# hulls.
Pulled tubing to 2026' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1192' - pumped 100 sxs cement with 100# hulls - circulated cement.
PTOH. Squeezed 5 1/2" casing with 50 sxs cement.
Max. P.S.I. 350#. S.I.P. 300#.
Hooked up to backside and pumped 50 sxs cement.
Max. P.S.I. 150#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3822	3950		

INVOICED
DATE 3/25/10
INV. NO. 2010060975

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 08 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM