

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20716-00-00
Spot: E2NENE Sec/Twnshp/Rge: 25-10S-24W
4620 feet from S Section Line, 330 feet from E Section Line
Lease Name: MABELLE Well #: 3
County: GRAHAM Total Vertical Depth: 4028 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3962		
SURF	8.625	165	0	150 SX
PROD	4.5	4028	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/22/2010 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 4% gel - 600# hulls.
Tubing and rods at 2180' - unable to fish.
No squeeze records. Perforate at 2023' and 1200'.
Production perfs: 3782' - 3952'. CIBP at 3960'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/22/2010 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 2023' and 1200'.
Ran tubing to 2150' - pumped 75 sxs neat - followed with 75 sxs cement with 200# hulls.
Pulled tubing to 1210' - pumped 165 sxs cement with 300# hulls - circulated cement to pit.
PTOH. Topped 4 1/2" casing off with 10 sxs cement. Casing full.
Hooked up to backside. Pumped 25 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3966	3972		LKC 'L'
3946	3952		LKC 'K'
3924	3932		LKC 'J'
3901	3911		LKC 'I'
3886	3891		LKC 'H'
3828	3834		LKC 'F'
3820	3822		LKC 'E'
3782	3786		LKC 'B'

INVOICED
DATE 3/25/10
INV. NO. 2010060975

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 08 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM