

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01727-00-00
Spot: SWNENW Sec/Twnshp/Rge: 19-9S-20W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: TURNER Well #: 1
County: ROOKS Total Vertical Depth: 3800 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	185	0	100 SX
PROD	5.5	3794	0	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2010 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 800# hulls - 9 sxs gel.
Fluid level 950'. Perforated at 2196' - 971' - 160'.
Holes from 3290' - 3351' and 1583' - 1614'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/15/2010 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3725' - pumped 9 sxs gel spacer - followed with 70 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 2160' - pumped 110 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1075' - pumped 100 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 25 sxs 60/40 pozmix - 4% gel with 50# hulls.

Perfs:

Top	Bot	Thru	Comments
3794	3800		ARBUCKLE
3780	3873		LKC
3678	3683		LKC
3660	3662		LKC
3595	3599		LKC
3582	3584		LKC
3548	3551		LKC
3506	3509		LKC

INVOICED
DATE 3/25/10
INV. NO. 2010060975

RECEIVED
MAR 22 2010

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #039141.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

MAR 17 2010

PALMER OIL CORP. ET AL

#1

TURNER

19-9-20W 22
SW NE NW

Contr. MUSGROVE PETROLEUM CORPORATION

ROOKS

Coun

E 2256RB

Comm.

Comp.

4-13-51

IP

3000. BOPD

ECHO

Tops	Depth	Datum
HEEB	3469	-1213
LANS	3508	-1252
ARB	3793	-1537
T.D.	3800	-1544

Casing

8" 185

ACID 500

5" 3794

GRA=ROOK POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS