

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24826-00-00
Spot: SWNWENW Sec/Twnshp/Rge: 27-16S-21W
4821 feet from S Section Line, 3832 feet from E Section Line
Lease Name: HINMAN 'WG' Well #: 1-27
County: NESS Total Vertical Depth: 4250 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224		WITH 160 SX CMT
PC		1604		CEMENTED WITH 140 SX CMT. 10 SX CMT CIRCULATED TO PIT
PROD	4.5	4246	0	WITH 185 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2010 11:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: PUMP 100# HULLS, 25 SX CMT, MUD SPACER TO 1600'. CMT FROM 1600' TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2010 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 25 SX CMT & 100# HULLS, THEN 12 SX GEL, THEN PUMPED 100 SX CMT. PRESSURED TO 400#. WENT ON VACUUM. BACKSIDE WAS FULL OF CMT. TOOK SWEDGE OFF & TOPPED OFF WITH 20 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4160	4164		CHEROKEE A SAN

INVOICED
DATE 3/25/10
INV. NO. 2010060979

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 08 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED

MAR - 2 2010

KCC DODGE CITY