

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22482-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 5-14S-17W
5043 feet from S Section Line, 2434 feet from E Section Line
Lease Name: DINKEL EAST Well #: 1
County: ELLIS Total Vertical Depth: 3550 feet

Operator License No.: 5386
Op Name: PRODUCTION DRILLING, INC.
Address: 1023 RESERVATION RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200	0	w/unknown sxs cmt
PROD	4.5	3549	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2010 2:00 PM
Plug Co. License No.: 5386 Plug Co. Name: PRODUCTION DRILLING, INC.
Proposal Rcvd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING, INC. Phone: (785) 625-1189

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 4% gel - 600# hulls.
Bad casing from 850' to 1980'. Out of 4 1/2" casing at 1980' - decided to P/A.
CIPB 3500' approximately - Arbuckle 3550' - 3580'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2010 4:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

02/24/2010 - Perforated two holes each at 600' and 1245'.
Ran tubing to 1956'. Quality Oil Well Cementing pumped 200 sxs 60/40 pozmix - 4% gel - good circulation drilling mud.
Pulled tubing to 1250'. Quality Oil Well Cementing pumped 100 sxs 60/40 pozmix - 4% gel with 600# hulls.
Circulated cement - stuck tubing backed off tubing.
PTOH. Left 25 joints tubing in hole (approximately 725').
Dug out backside and pumped 50 sxs cement down.
Max. P.S.I. 350#. S.I.P. 300#.
03/02/2010 - Checked cement in 4 1/2" casing. 310' from surface.
Topped off 4 1/2" casing with 1.25 yard of Redimix. No sand aggregate - casing full.

Perfs:

Top	Bot	Thru	Comments
3300	3510		

INVOICED
DATE: 3/25/10
INV. NO. 2010060980

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 08 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

WEILERT ENTERPRISES
HAYS KS5-14S-17W
250°FNL & 2310°FEL, SEC

#1 DINKEL EAST

site: 3-1/2 S & 1/2 W OF CATHERINE KS

cty: ELLIS

API 15-051-22482

contr: HELBERG OIL CO

field: YOUNGER

geol:

fr
date 07/01/81sp
date 07/15/81drig
comp 07/20/81card
issued 01/07/82last
revised 07/05/99

ELV: NA

tops.....depth/datum

RTD.....3550

NO TOPS RPTD

IP status:

OIL, P 28 BO & 4 BWPD, ARB, INTV NA, 10/30/81

CORR & INFO REL: 7/5/99 - REDESCRIBED LOC; WAS
OIL WELL - TEMP COMP

CSG: 8-5/8" 200+, 4-1/2" 3549

COMMENT: REDESCRIBED LOC - IS ALSO 250°FNL &
330°FNL, NW NE

NO CORES OR DSTS RPTD

MICT - CO, PF (ARB) INTV NA, SWB DWN, GSO, NAT,
POP, IPP 28 BO & 4 BWPD, 10/30/81 - NO OTHER INFO
RELEASED BY OPERATOR OR ON KCC RECORDS; ALL
REQUESTS FOR INFO DENIEDCOPYRIGHT 1999
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS