

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21820-00-00
Spot: NESWSE Sec/Twnshp/Rge: 35-23S-5E
694 feet from S Section Line, 1427 feet from E Section Line
Lease Name: JANZEN Well #: 6
County: BUTLER Total Vertical Depth: 2630 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N MARKET ST STE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	166		100 SXS
PROD	4.5	2629	825	75SXS

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2010 12:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

3/4/10 RANGE CALLED IN FOR PLUGGING ORDERS ON WELL. THEY EITHER HAD COLLAPSED CASING OR WERE OUT SIDE OF THE CASING WITH TUBING AND BIT. THEY ARE ONLY ABLE TO GET TO APPROX 1608' AND WANT TO PLUG FROM THIS POINT. IT WAS DISCUSSED TO LET THEM PLUG AT THIS POINT. 3/5/10 PHILLIPS RAN TUBING DOWN TO 1611' AND CONSOLIDATED PUMPED 35 SXS OF COMMON W/3% CC. PHILLIPS PULLED THE TUBING. CONSOLIDATED RAN ITS WIRE LINE DOWN TO TAG PLUG @ 1206'. SHUT DOWN FOR THE WEEKEND. THEY USED 35 SXS COMMON W/3% CAC1 TK# 3/8/10 DYNA-LOG RAN IN AND SHOT OFF 4.5 @ 825'. PHILLIPS LAID OUT CASING (19 JOINTS). PHILLIPS THEN RAN IN TUBING TO APPROX 253'. CONSOLIDATED TIED ON AND CIRCULATED WATER TO SURFACE. THEY THEN SWITCHED OVER TO CEMENT AND CIRCULATED CEMENT TO SURFACE. PHILLIPS PULLED TUBING, AND CONSOLIDATED TOPPED OFF THE HOLE. THEY FINISHED UP AROUND NOON. THEY USED 131 SXS OF 60/40 POS W 4% GEL TK # 23393.

Perfs:

Top	Bot	Thru	Comments
2488	2562	CSG	

INVOICED
DATE: 3/25/10
INV. NO. 2010060982

RECEIVED
MAR 11 2010
KCC WICHITA

Remarks: EMERGENCY PLUGGING NO CP-1. WELL HAD DENIED TA DUE TO CASING LEAK. WELL INFORMATION FROM DENIED CP-111 APPLICATION.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

15